



CONCEPT, NOT FOR FABRICATION

AirStreet · github.com/BoujeeEnjinia1701/airstreet



TOP VIEW

Scale 1:10; looking down (along -Z)




FRONT VIEW

Scale 1:10; looking at the front (along +Y)

RIGHT VIEW

Scale 1:10; looking at the right side (along -X)



ISOMETRIC VIEW

Not to scale; pole stub shown; seen from the front right and above, about 30 deg elevation

MAIN DIMENSIONS AND INTERFACES (MM)

Pole 80 to 200 OD (design 140); two 12.7 stainless band clamps 375 apart, V-saddles
Rail 40 x 5 x 565; enclosure on it, no back plate; adapters 180 x 25 x 3
FieldNode core 150 x 90 x 200, underside 3,230; 6 W panel at 40 deg
Pod 170 x 110 x 95, open underneath behind mesh; drip lid +15 each side
Inlet plane 3,000 above sidewalk, chain line in front view (EU 1,500 to 4,000)
Shield 8 plates 120 OD at 13 pitch, 200 from pole axis, 176 from pole face; T and RH probe at 3,032
M12 port A (switched 5 V): SPS30 and SHT45; port B (5 V held on): NO2 front end
FieldNode whip at x = 58, 23 clear of the pod lid
Mass 3.26 kg, frontal area 0.126 m² (AST-CAL-001 v0.2; R13 met on paper)
Third-angle; front view from the street (-Y); pole on the Z axis

AIRSTREET

github.com/BoujeeEnjinia1701/airstreet

General arrangement

DRAWING NO. AST-DWG-001			REV P3	SHEET 1 of 1	SIZE ANSI B
SCALE 1:10	UNITS mm	PROJECTION 	DATE 2026-09-25	DRAWN Amish Chadha	

MATERIAL / NOTES

FieldNode core per FND; bought-in parts per bom/bom.csv. PRELIMINARY, NOT FOR FABRICATION